



**ADDENDUM #2**  
**200 EAST TRENCHLESS SEWER REHABILITATION PROJECT**

The following changes are hereby made to the Contract Documents for the above referenced Project:

1. The measurement and payment and Addendum #1 item for sewer lateral reinstatement is incorrect. Please use the following for MP111a

MP111a	Connection of Existing Sewer Lateral to Existing Pipe
<p>Measurement and payment for this item shall be on a per each basis. Service connection and lateral reinstatement is to be made internally with appropriate remotely operated equipment. Excavation of connections of laterals is not allowed. Restored connection or lateral openings are to be cut neatly to full size without over-cutting. Cuts shall be smooth and without residual material left around the opening. Ragged edges or attached material are not allowed. T-liner or fully sealed connection from lateral to main required.</p> <p>Work shall progress and continue promptly to minimize downtime on pipelines and out-of-service laterals.</p> <p>The contractor is responsible to make sure all active service laterals are reconnected. Where lateral flow has been interrupted, reinstatement of the lateral shall proceed as soon as possible. Laterals may be reinstated using an initial opening sufficient to restore flow, followed by completion to full reinstatement of 100% open within 8 hours.</p>	

2. Section 02765 (Pipe Rehabilitation by UV cured-in-place pipe (CIPP) Process) Part 2.1 E Lateral Seals should read: 1. ASTM F2561 compliant LMK T-Liner or equivalent lateral sealing system shall be used to reconnect existing service laterals.

This Addendum is hereby attached to and made part of the Bidding Documents and each Bidder shall acknowledge receipt of this Addendum on the Bid Form.

---

**Project Engineer:** Brett Jones, P.E.  
Jones & Associates  
6080 Fashion Point Drive

